



## FERRY BOW DECK SPUD BARGE ML - 900

DIMENSIONS		SPECIAL EQUIPMENT	
LENGTH	126 ft 38.4 m	SPUD WELLS (2)	22 in
BEAM	30 ft 9.14 m	ROUND BOW	YES
DRAFT	1 ft 6 in .457 m	ROLL ON ROLL OFF	YES
FREEBOARD	6 ft 6 in 1.98 m	MOON POOL	NO
CARGO DECK		GENERAL	
TONNAGE	115 Ton/Draft-ft 104 LT/Draft-ft	OWNER	MILLER LAUNCH INC
LENGTH	120 ft 36.5 m	BUILDER	
WIDTH	30 ft 9.14 m	YEAR BUILT	
CLEAR SPACE	3600 sqft 334 sq m	OFFICIAL NUMBER	
TONNAGE		FLAG	USA
		USCG	
GROSS TONNAGE			260 Ton
NET TONNAGE			260 Ton
OPTIONAL EQUIPMENT			
SPUD WINCH			
NO			
SPUDS (2)			
20 in x 65 ft			
CRANE			
NO			
HPU			
NO			